



10633 County Road 26  
 Blair, NE 68008  
 Phone: 402-571-1303  
 Fax: 402-502-6662

# Quotation

DATE: 6-10-2025  
 QUOTE # 251006-00

Please address purchase orders to:  
**GPM Environmental Solutions, LLC**

**Quotation Prepared For:**

Dale Klussman  
 City administrator  
 City of Concordia  
 618 S. Main St.  
 Concordia, MO 64020  
 P. 660-463-2228  
[administrator@concordiamo.org](mailto:administrator@concordiamo.org)

**RE: Metering Manhole with 63 Parshall Flume**

Item	Qty	Part Number	Description	Unit Price	Total Price
1	1	PMM-10FT_3PAR	<p><b>Packaged Metering Manhole – 60" Ø x 10'-0" Deep (invert to grade). Includes 2" threaded coupling, Integral Ladder, FRP Dome Cover, Base Mounting Flange, and Floor.</b></p> <p><b>ACCESS</b></p> <ul style="list-style-type: none"> <li>-Aluminum Hatch - Halliday Products- Product C1R64 Cover Plate with 36" x 36" F1R Watertight</li> <li>Aluminum Hatch- Finished at Finished Grade</li> </ul> <p><b>FLUME</b></p> <p><b>-3" Parshall Flume</b></p> <ul style="list-style-type: none"> <li>-Inlet and Outlet End Adapters with (2) 8"Ø Pipe Stubs</li> <li>-(2) 8"Ø Fernco Couplers with Stainless Steel</li> <li>-(1) C-Channel for GPM Ultrasonic Mounting Bracket</li> <li>-(1) 316SS Bubbler Tube</li> <li>-(1) 316SS Sampler Tube</li> <li>-(1) English Staff Gauge – Graduated in Feet, Tenths, and Hundredths</li> </ul> <p><b>CONSTRUCTION</b></p> <ul style="list-style-type: none"> <li>-Fiber-Reinforced Plastic (FRP) Construction</li> <li>-Isophthalic Polyester Resin</li> <li>-UV Resistant Gel Coat Surface – Beige TYP (Flume, Dome Cover)</li> <li>-UV Resistant Gel Coat Exterior - White TYP (Manhole Basin)</li> <li>-Resin Rich Interior – Natural Finish (Manhole Basin)</li> <li>-1/4" Laminate Thickness (Flume, minimum)</li> <li>-1/2" Wall Thickness (Manhole Basin, minimum)</li> </ul> <p><b>FLOW RATES : 3 inch Parshall</b></p> <p><b>-Minimum: 12.63 GPM -Maximum: 833.60 GPM</b></p>	\$22,800.00	\$22,800.00

2			<p><b>Continued -</b></p> <p>NOTES</p> <ul style="list-style-type: none"> <li>-Flume will have integrally bonded pipe stubs to accommodate inlet and outlet pipes at established elevations.</li> <li>-Contractor to confirm elevations prior to production.</li> <li>-Depth of manhole subject to change based on pipe elevations.</li> <li>-Standard installation parameters still apply.</li> <li>-Consult VPC for upstream, downstream, and pipe slope requirements.</li> <li>-Recommendations to be reviewed by project engineer for accuracy, performance, and compliance.</li> </ul>		
<b>Fiberglass Shelter Building</b>					
3	1	END600	<p><b>Enduro Model 600. Insulated Shelter (R14 Minimum).</b> 72 x 72 x 84" Tall. Single Door Access. Includes Standard Stainless Steel Hardware, Fixed Louver Ventilation, and Set of Stainless-Steel Lifting Eyes.</p> <p><b>ACCESS</b></p> <ul style="list-style-type: none"> <li>-Single Door Access</li> <li>-Lockable T-Handle</li> <li>-Door Closer</li> <li>-Door Sweep</li> <li>-Drip Edge</li> </ul> <p><b>CONSTRUCTION</b></p> <ul style="list-style-type: none"> <li>-Fiber Reinforced Plastic (FRP) Construction</li> <li>-Isophthalic Polyester Resin</li> <li>-UV Resistant Gel Coat Exterior (Beige TYP)</li> <li>-UV Resistant Gel Coat Interior (White TYP)</li> <li>-1" Rigid Polyiso Insulation (R7)</li> </ul>	\$8,200.00	\$8,200.00
<b>Ultrasonic Flowmeter</b>					
4	1	684310000	<p><b>ISCO Signature® Ultrasonic flowmeter system.</b> Starting price includes base station 624300005, TIENet 310 ultrasonic level sensor with 32.8 ft (10 m) cable.</p>	\$5,200.00	\$5,200.00
5	1	604304069	<p>ISCO TIENet® 304 contact output option card, two isolated independent Form C relay circuits.</p>	\$438.00	\$438.00
6	1	604307018	<p>ISCO TIENet® 301 pH and temperature sensor interface with 32 ft (10 m) long cable. Includes pH and temperature sensor (60-9004-126) with 25 ft (7.6 m) cable, calibration buffers and electrode rinse solution for initial commissioning.</p>	\$2,150.00	\$2,150.00
7	1	604307108	<p>ISCO LTE Global cellular modem with magnetic mount antenna for Signature® meter. Hardware.</p> <p>(Three bolded line items 6-8 must be ordered together)</p>	\$1,556.00	\$1,556.00

8	1	CELLSERVICE	ISCO First year ICell subscription for Cellular service with 10MB/month data and 25 SMS/month. <u>Price is per site per year.</u>	\$600.00	\$600.00
9	1	682541001	ISCO Flowlink Cipher for up to 9 active sites. <u>Price is per site per year.</u> Please multiply with number of sites.	\$600.00	\$600.00
10	0	SOLAR40	<b>Solar Power</b> 40 watt solar panel, regulator, cables to meter and battery, stainless enclosure for flowmeter display and battery and marine GEL cell battery.	\$3,570.00	<b>\$0.00</b>
<b>Automatic Refrigerated Sampler</b>					
11	1	685800001	5800 Refrigerated Sampler (115 VAC, 60 Hz). Includes control panel, refrigeration unit, distributor arm, and two pump tubes.	\$9,857.00	\$9,857.00
12	1	685800005	4-bottle Configuration. Includes four polyethylene 10-liter (2.5 gallon) round bottles with caps, locating base and two discharge tubes.	\$749.00	\$749.00
13	1	685800015	24-bottle Configuration. Includes 24 polypropylene 1-liter wedge shaped bottles with caps, bottle rack and two discharge tubes.	\$645.00	\$645.00
14	1	681680058	3/8 inch vinyl suction line - 100 ft. Includes tubing coupler.	\$145.00	\$145.00
15	1	692903138	3/8 inch stainless steel strainer, low flow.	\$103.00	\$103.00
16	1	606700062	Pump tubing for 5800/4700 and 6700 Series/Avalanche Sampler - quantity 5	\$194.00	\$194.00
17	1	685800020	5800 refrigerated sampler multipurpose cable with 16 unterminated leads, 10 ft. (3 m).	\$209.00	\$209.00
18	1	EXCAVATE/INST ALL	<b>Excavation and complete installation</b> of new fiberglass metering manhole provided herein, by GPM Environmental. 1. Excavate, pour base pad concrete to specification by flume manufacturer. 2. Day 2, start bypass pumping OR stop flow, cut out pipe section and place manhole. Make connections to existing sewer. Re-establish flow in sewer. 3. Coordinate conduit from manhole to site for shelter building. 4. Backfill and grade. 5. Pour pad for 6x6 shelter that is 8x8 in dimension, and mount the Flowmeter with Sampler.	\$15,270.00	\$15,270.00
19	0	SUPERVISOR	Supervisory presence for excavation, concrete base prep and installation of new fiberglass metering manhole quoted herein. Includes time and travel for (4) 8 hr days. 7 AM-4PM. Additional days at \$856/day	\$3,584.00	<b>\$0.00</b>
20	1	METER-START	Startup and training for new flowmeter. Includes programming, analog output setup and calibration, with documentation/REPORT.	\$1,500.00	\$1,500.00

Subtotal	\$70,216.00
Freight/Crate	\$5,251.00
	\$75,467.00

**TERMS AND CONDITIONS:**

1. Prices Valid 30 Days
2. NET 30 - As supplies are delivered, progress invoices will be sent.
- 3. Initial 25% general payment due upon order. GPM to produce an invoice in the amount of \$18,867.00 upon order receipt.**
4. Freight Included here, tax extra.
5. Delivery of Metering Manhole ~8 weeks after drawing approval. 4 weeks with expedite, Flow meter @2 weeks.
6. Insurance accord for GPM to be provided upon execution of contract.

*Customer Acceptance (sign below):*

x \_\_\_\_\_  
Accepted by: Title: Date: PO#

If you have any questions about this price quote, please contact:

**Justin Meader - P. 402-571-1303 - [justin@gpmweb.net](mailto:justin@gpmweb.net)**

***Thank You For Your Business!***